


RESTROOM PLUMBING FIXTURES (PER TABLE 29-A)						
OCCUPANT LOAD (PER TABLE 1004.5)						
M = 29,823 SF / 600 = 497						
B = 1,143 SF / 150 = 8						
S1 = 11,248 SF / 300 = 38						
TOTAL OCCUPANTS = 543 (211M / 211F)						
REQUIRED:						
	MEN	WOMEN		MEN	WOMEN	UNISEX
W.C.	2	2	W.C.	1	2	1
URINAL	1	-	URINAL	1	-	-
LAVATORY	2	2	LAVATORY	2	2	1


Requirements for delayed egress locking system:

1. The delay electronics of the delayed egress locking system shall deactivate upon actuation of the automatic sprinkler system or automatic fire detection system, allowing immediate free egress.
2. The delay electronics of the delayed egress locking system shall deactivate upon loss of power controlling the lock or lock mechanism, allowing immediate free egress.
3. The delayed egress locking system shall have the capability of being deactivated at the fire command center and other approved locations.
4. An attempt to egress shall initiate an irreversible process that shall allow such egress in not more than 15 seconds when a physical effort to exit is applied to the egress side door hardware for not more than 3 seconds. Initiation of the irreversible process shall activate an audible signal in the vicinity of the door. Once the delay electronics have been deactivated, rearming the delay electronics shall be by manual means only. (Exception: Where approved, a delay of not more than 30 seconds is permitted on a delayed egress door.)
5. The egress path from any point shall not pass through more than one delayed egress locking system.


Location of the manual deactivation of the delayed egress locking system to be a deferred submittal



E1 FIRE LIFE SAFETY PLAN - GARDEN CENTER
SCALE: 3/32" = 1'-0"




C3 EGRESS LIGHTING PATH
SCALE: N.T.S.



E4 FIRE LIFE SAFETY PLAN - HAY SHED
SCALE: 3/32" = 1'-0"

SHEET NOTES



WILCO EUGENE
WILTH & WILLOW CREEK
EUGENE, OREGON 97402

WILCO
200 INDUSTRIAL WAY
MT. ANGEL, OR 97362

project number 18-25
date 10/03/22

revisions

- 1 06/02/23 AGENCY REVIEW
- 2 07/10/23 AGENCY REVIEW 2
- 3 08/01/23 AGENCY REVIEW

KEY NOTES

- 1 EXTEND FIRE SPRINKLERS INTO GARDEN CENTER
- 2 ALL THROUGH PENETRATIONS AND DUCTS OF EXTERIOR WALLS INTO GARDEN CENTER TO BE PROTECTED BY AN APPROVED PENETRATION FIRESTOP SYSTEM, PER OBC 114



FIRE LIFE SAFETY
PLAN -
GARDEN CENTER

sheet number

FLS02

